



Burns Mechanical Company
 9913 State Hwy 72, Patton, MO 63662
 573-944-3144 garret@burns-mech.com
 573-282-9788 greg@burns-mech.com

Proposal To: Mike/Matt

Ste. Genevieve School
 715 Washington St
 Ste. Genevieve, Mo 63670

Quote Details: Burns Mechanical Company is pleased to quote the replacement of the 30 ton CU and DX coil at the Middle School 2 story building.

Scope of Work:

- Remove existing Condensing unit.
- Install new DX coil, refrigeration piping and one (1) Daikin 30 ton condensing unit. New CU and system is 410a Refrigerant.
- Rework roof curb to accommodate new condensing unit.
- Refrigeration piping to be insulated with min 1/2" Armaflex.
- Rework control wiring for the added stage control on new system.
- Start up and commissioning.

Note: IFS to do the upgrade of controls to accommodate staging control.

Warranty:

- Labor warranty is one (1) year from completion date.
- Parts warranty is based on manufacturer's warranty.

Terms:

- 50% payment due upon signing of the quoted proposal.
- 50% payment due upon completion of installation.

Total cost for this proposal with Daikin Equipment: \$ 80,850.00

Note: Estimated delivery for Daikin equipment is approximately 12 weeks.

Prepared by: Greg Burns

Owner Acceptance:

Date: 11 June, 2025

Date _____

Note: This quote is good for 30 days from date above.



THANK YOU FOR THE OPPORTUNITY TO SUBMIT THIS PROPOSAL.

Installation Shall Not Include:

- Any fire protection work, i.e. sprinkler system piping, fire alarm system.
- Any cutting, removal, replacement, or patching of roof, wall, floor, or ceiling.
- Any painting of exposed or concealed, insulated or un-insulated, piping, ductwork, or conduit.
- Any concrete pads, structural, seismic, housekeeping, equipment, etc.
- Any performance / payment bonds.
- Any premium time work.
- Any duct work removal, changes, or installation.

Installation Shall Include:

- Reworking of the power and control wiring for proper connection at new equipment
- Reworking of Refrigeration and drain piping to new system
- Removal and disposal of existing equipment