

G. F. GARCIA & SONS, INC.

GENERAL ENGINEERING CONTRACTORS

P.O. Box 525, Cayucos CA 93430

Phone (805) 995-3548 – Fax (805) 995-1895

Lic. 736277, SBA# 41625, DBE: UCP Firm No.40744 DIR #:1000006462

Proposal for Site Work

To: PRJUSD

Date: 6/2/2023

Attn: Britiany Baker bbaker@pasoschools.org

Project: Georgia Brown exploratory trench

GFGSI Job No: 23-1153

Qualifications:

G.F. Garcia & Sons proposes to furnish labor, materials and equipment to perform the following scope of work per emailed attachment. GFGSI is non-union, skilled and trained workforce, and a certified DBE (UCP firm No. 40744). Pricing per specified wage determination

*Pricing below is based on utilization of on-site soils with optimal or below moisture content at time of grading. If rain events create conditions where site soils are over optimal moisture as determined by Soils Engineer any soils removal, non-expansive import or soil treatments will be billed on a time and materials basis.

Scope:

Excavation to +/- 25' depth, shoring, site safety fencing, backfill, site cleanup, fence replacement, irrigation replacement and maintenance, and hydroseeding

Includes:

- Mobilization
- +/- 20 lf fence removal and replacement at access point
- Site safety fence (to remain 30 days after hydroseed)
- Pothole irrigation, and removal of sprinkler heads
- Excavation of bulk dirt
- Dig and shore bottom at vertical cut
- Backfill
- Site finish grade and clean up
- Irrigation replacement including new main line and branch lines, new valve kits including control wiring, new sprinkler heads, and coverage testing before seeding. (Existing controller to be reprogrammed with district representative present)
- +/- 60,000 sqft of hydroseeding with "Grand Slam Perennial Rye Turf Seed Mix"

Excludes:

- AC replacement at access point due to unknown condition
- Relocation of existing unknown utilities excluding irrigation
- Import if needed, site to balance

Any work not specified, bonding, surveying, testing, permits or fees, engineering or associated fees, hazardous material testing or removal, archaeological survey or mitigation, haul off of spoils or trash generated by others, SWPPP/WPCP design or implementation and traffic control.

Miscellaneous Qualifications:

Due to the recent fluctuations in the price of oil, prices for asphalt and road base have been subject to unexpected and severe increases. In the event the proposal has been accepted, but the work not performed within 30 days, the price set forth herein shall be subject to either increase or decrease in like amount as any such increase or decrease in the price of asphalt which is required for the work described herein.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our employees are covered by Workman's Compensation Insurance. Owner to bear costs of reparation, legal fees and fines if specified wage determination is deemed incorrect.

Lump Sum Quote/Itemized Total: \$293,865.00

This pricing may be withdrawn by us if not accepted within (30) days.

Payment Terms: Monthly Progress Payments

This quote is conditioned on: a mutually acceptable form of Purchase Order or contract document incorporating this proposal. Please call Alec (805-441-1860) if you have any questions.

Alec Garcia, CEO